

SECTION 9 – PREINSTALLATION CHECKLIST

TABLE OF CONTENTS

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE</u>
9-1	INTRODUCTION	9-3
9-2	PREPARATIONS REQUIRED IN ADVANCE OF UPGRADE DELIVERY	9-3
9-3	GENERAL PREINSTALLATION REMINDERS	9-4

9-1 INTRODUCTION

“Preinstallation” refers to work necessary to plan and prepare a site for delivery and installation of equipment. Delay, confusion, and waste of manpower can be avoided by completing preinstallation work.

The purpose of this section is to outline key areas of concern in the preparation of a customer's site for Signa Horizon upgrade. It is intended as a guide for GE's Installation Specialists and/or Installation Leaders when making on-site inspections during the installation planning phase of the upgrade. Note site inspections by GE are intended to aid the overall site preparation process. They do not relieve the customer and project architect from responsibility for the design, engineering, and coordination efforts necessary to ensure a successful MR project.

During the course of the site preparation process, GE's Installation Specialists and/or Installation Leaders may observe that the Requested Arrival Date (RAD) for the upgrade equipment is not realistic. If this is the case, appropriate actions must be taken by the GE Field Sales/Service Team to adjust the RAD accordingly.

All work must be in compliance with national and local safety codes.

9-2 PREPARATIONS REQUIRED IN ADVANCE OF UPGRADE DELIVERY

The following items must be completed by the installation Specialist or Site Field Engineer prior to upgrade equipment delivery. An on-site inspection by a GE Representative to confirm site readiness must be completed at least 2 weeks prior to the Scheduled Arrival Date (SAD) of the upgrade equipment.

- ☐ 1. There is not an upgrade ordering checklist document for LCC Magnet WideOpen Enclosure upgrades. Therefore, refer to catalogs information in Section 1 SYSTEM CONFIGURATION to confirm correct order information has been submitted to Americas Customer Center, ATTENTION: Bob Healy (FAX number 414-827-3348) at least 4 weeks prior to SAD.
- ☐ 2. Has a site equipment plan been completed, reviewed with the customer, and finalized?
- ☐ 3. Has a cable routing plan been completed? Are all cable lengths sufficient? If lengths are not sufficient, a Special Order Inquiry (SOI) will be required. Contact Rich Holly at 414-521-6168 at least 8 weeks prior to SAD to allow for proper processing of the request.
- ☐ 4. Does the site's HVAC (heating, ventilation, and air conditioning) system meet requirements in Section 4-2, TEMPERATURE AND HUMIDITY SPECIFICATIONS, and Section 4-3, COOLING REQUIREMENTS, of this document? If these specifications are not strictly adhered to, failure of the SGD Gradient Cabinet modules may occur.
- ☐ 5. Has delivery route been defined for equipment especially enclosure covers (refer to Section 2-2, MINIMUM DOOR SIZES) including plans for protecting flooring for heavy equipment & carts (ie. RF/Gradient Body Coil & installation cart)?

9-2 PREPARATIONS REQUIRED IN ADVANCE OF UPGRADE DELIVERY (Continued)

- ☐ 6. Have all upgrade exceptions, such as special cabling and options unique to the site including customer equipment, been identified and clearly tagged **DO NOT REMOVE** ?
- ☐ 7. Has a holding area for old equipment and installation debris been agreed upon with the customer? Making provision for a holding area will allow for efficient unloading and reloading of the delivery vehicle.

9-3 GENERAL PREINSTALLATION REMINDERS

- ☐ 1. Have vehicle parking arrangements been made for installation personnel?
- ☐ 2. Is temporary storage space available for use during installation?
- ☐ 3. What is hospital smoking policy?
- ☐ 4. Are a first aid kit and non-ferrous fire extinguishers available at site?
- ☐ 5. Have facility arrangements been made for refuse disposal during installation?