

HEC Coolant Fill and Coolant Leak Check

[\(Click here for Summary Version\)](#)

1 Personnel Requirements

Required Persons	Preliminary Reqs	Procedure	Finalization
1	Not Applicable	90 mins	Not Applicable

2 Overview

The HEC Coolant Fill and Coolant Leak Check procedure demonstrated how to properly fill the Gradient Coil and Power Electronics tanks with a deionized water solution within the HEC (Heat Exchange Cabinet). Usually, the Gradient Coil tank is filled before the Power Electronics tank.

IMPORTANT: Examine the two Ball (shut-off) Valves and two Check Valves for leaks prior to filling the system with coolant to avoid potential equipment damage and customer dissatisfaction.

3 Preliminary Requirements

3.1 Tools and Test Equipment

Item	Qty	Effectivity	Part#	Manufacturer
5 gallon Pail	1	-	-	-

3.2 Consumables

Item	Qty	Effectivity	Part#	Manufacturer
Coolant (see Step)	60 one-gallon containers	-	5174313	-

Illustration 1: One Coolant Gallon



Note: The coolant fluid is dyed for easy detection of leaks. This also helps to distinguish between a leak and any normal condensation on the hoses.